■ legrand

Legrand cabling system LCS²
category 6
patch panels, blocks of connectors

NEW

0 335 62

0 335 90

0 335 89

0 335 65

Cat. 6 connector
STP shielded

Pack	Cat.Nos	**Patch panels cat. 6** **24 x RJ 45 quick-fixing connectors**
		Panels supplied with quick-fixing Panels ensure automatic grounding of each connector Fitted with rear cable guide to hold cables during maintenance Fitted with 4 units of 6 LCS² RJ 45 connectors cat. 6 with fast connection thanks to integrated crimping, with colour code and wiring schemes T 568 A and T 568 B Supplied with numbered colour labels Conform to standards ISO/IEC 11801 Ed. 2.0, amendment 2, EN 50173-2 and TIA/EIA 568C 19" panel - 1 U
1	0 335 61	UTP panel - 8 contacts
1	0 335 67	UTP high density panel - 8 contacts
1	0 335 62	FTP panel - 9 contacts
1	0 335 68	FTP high density panel - 9 contacts
1	0 335 63	STP panel - metal shielding 360°
		UTP through panel 24 x RJ 45 connectors
1	0 335 89	UTP through panel

Pack	Cat.Nos	**Modular panels**
		Panels supplied with quick-fixing General all-purpose assembly of all enclosures or cabinets Panels ensure automatic earthing of each connector Fitted with rear cable guide to hold cables during maintenance Empty panels to be fitted with 4 units Take the following equipment: - 6 LCS² RJ 45 connector units - telephone inlet units - fibre optic units - PoE injector units - video streaming units - switch units - telephone/Ethernet doubler units - copper/fibre optic converter units - blanking plates
1	0 335 90	19" panel - 1 U

		Units of 6 x RJ 45 connectors cat. 6
		Fitted with 6 x LCS² RJ 45 connectors cat. 6 with fast connection thanks to integrated crimping, with colour code and wiring schemes T 568 A and T 568 B Supplied with colour labels Conform to standards ISO/IEC 11801 Ed. 2.0, EN 50173-1 and TIA/EIA 568
2	0 335 64	UTP unit - 8 contacts
2	0 335 65	FTP unit - 9 contacts
2	0 335 66	STP unit - metal shielding 360°
10	0 335 91	Blanking plate for 19" panel - Black

Red catalogue numbers: New products